



NOTICE TO ALL FIRMS

Date: April 25, 2024
To: All Prospective Bidders
From: Sam Li
Interim Director of Procurement Services
Re: Addendum Number 2
IFB # C1622 – COED Residence Hall Rooms & Corridors Painting, Floors 6-9

Questions

- Q1. What are the wall finishes for the bathrooms? The drawings says walls painted but according to walk-through pictures, my PM took the bathroom seems to have tile walls.
A1. **Painting in the bathrooms to be on the ceiling only. Existing walls are finished with tiles (floor to ceiling). Ceiling to be painted with P1 semi-gloss.**
- Q2. Can you clarify the extent of the work for the closet headers?
A2. **The headers of some of the existing closets are separated from the ceiling and walls, see attached photo. Header to be temporarily stabilized with 2x4 supports. Provide foam protection to prevent damage to existing walls to remain. A 4"x4" aluminum bracket to be used to secure the header into place at each end on the opening, see attached photo. Temporary supports are then to be removed. Contractor to assume 10 closets per floor will require additional support.**
- Q3. Want to confirm that there isn't any painting work at the stairwells, correct?
A3. **Confirmed. The fire stairs are not part of the scope of work. The corridor side of the stair door is to be painted.**

THIS ADDENDUM IS PART OF THE CONTRACT DOCUMENT AND SHALL BE INCLUDED WITH YOUR REQUEST FOR PROPOSAL SUBMITTAL. YOUR SIGNATURE BELOW WARRANTS THAT YOU UNDERSTAND THIS ADDENDUM AND THAT YOU HAVE MADE THE APPROPRIATE ADJUSTMENTS IN YOUR PROPOSAL AND CALCULATIONS.

Signature

Print Name and Title of Authorized Representative

Print Name of Company/Partnership/Individual

Date