



NOTICE TO ALL FIRMS

Date: April 19, 2024
To: All Prospective Bidders
From: Sam Li
Interim Director of Procurement Services
Re: Addendum Number 1
IFB # C1627 – Nagler Residence Hall Apartments & Corridors Painting, Floors 2-5

Questions

- Q1. Is the vinyl base required to be removed prior to painting?
A1. Exist. vinyl base is to remain and be protected during construction.
- Q2. Some of the corridor doors and also the apt bathroom door material is wood and not hollow metal. What are the finish requirements for the wood doors? Can you indicate which doors are wood vs hollow metal?
A2. The finish requirement for the wood doors is the same as for the HM. Clean, sand, prep, prime and paint with semi-gloss paint. Assume 25% of all doors are wood.
- Q3. Are the metal toilet stalls located in the women's restroom required to be painted?
A3. Toilet stall are to remain. Clean as required.
- Q4. Will we be allowed to paint the floors concurrently?
A4. Yes, work can occur concurrently on all floors. Upon substantial completion of a floor, Architect to punch list. Upon completion of punch list, turn the floor over to FIT for cleaning.

THIS ADDENDUM IS PART OF THE CONTRACT DOCUMENT AND SHALL BE INCLUDED WITH YOUR REQUEST FOR PROPOSAL SUBMITTAL. YOUR SIGNATURE BELOW WARRANTS THAT YOU UNDERSTAND THIS ADDENDUM AND THAT YOU HAVE MADE THE APPROPRIATE ADJUSTMENTS IN YOUR PROPOSAL AND CALCULATIONS.

Signature

Print Name and Title of Authorized Representative

Print Name of Company/Partnership/Individual

Date