



## NOTICE TO ALL FIRMS

Date: May 20, 2026  
To: All Prospective Bidders  
From: Sam Li  
Director of Procurement Services  
Re: Addendum Number 3  
IFB # C1746 – The Museum at FIT History Gallery Renovation

### Questions:

Q1. The architectural drawing (A-051) detail (2) calls for 3/4" clear tempered glass for the glass doors and glazed partitions at the vestibule, while the glazing schedule notes calls for 3/4" laminated glass with UV interlayer at the vestibule.

Please confirm the required glass type for:

1. Glass doors within the gallery partition
2. Any fixed glazed panels

Please advise whether the intent is:

1. 3/4" tempered glass, or
2. 3/4" laminated glass with UV interlayer

If laminated glass is required, please confirm performance requirements and interlayer type.

A1. Glass doors (D-01 & D-02) and glass within the Vestibule/Gallery partition and at the display niche should all be 3/4" laminated glass with UV interlayer. Please disregard the note on A-051 detail 2, which will be updated for the Construction Set.  
The glazing at the curtain wall windows (W1, W2, & W3) should all be clear insulated glass units.

Q2. May we substitute the manufacturer (Lite Lab) for lighting track and heads?

A2. We will not accept any substitutions. FIT Museum is matching an existing new system that they have in another gallery, which is also a Lite Lab system.

**THIS ADDENDUM IS PART OF THE CONTRACT DOCUMENT AND SHALL BE INCLUDED WITH YOUR REQUEST FOR PROPOSAL SUBMITTAL. YOUR SIGNATURE BELOW WARRANTS THAT YOU UNDERSTAND THIS ADDENDUM AND THAT YOU HAVE MADE THE APPROPRIATE ADJUSTMENTS IN YOUR PROPOSAL AND CALCULATIONS.**

---

Signature

---

Print Name and Title of Authorized Representative

---

Print Name of Company/Partnership/Individual

---

Date